BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No. RRND/EE/Tend/21/2019-20, Date: 04.03.2020

Indet No: BBMP/2019-20/RD/WORK_INDENT40910

SCHEDULE -B

Name of Work: Comprehensive Development of Roads, Drains, Special repairs to buildings and other works in Sunnadagoodu, Ambedkarnagar, Mohan Kumar nagar, Poornapura, Ramabhovi Colony, Jalahalli Harijana, Siddarthanagar, Khathanagar, Ashrayanagar, Karadigudi, Peenya 4th block A K Colony and Surrounding areas of Slums in R R Nagar Constituency under PACKAGE-2019-20 RRN-DIV-(13).

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	12.00	Geophysical investigation of site for Sinking borewell for supplying drinking water to the habitations either through the hand pump,MWS,P.W.S.S by vertical electrical sounding by adpoting venner or Schlumberger's method,including reconnaissance survey of Geological formation. Geophysical investigation of existing ground indecundity its quality & acceptability of the users indicating the location of site,recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 metre inconsolidated formation for proper seating of casing pipe,depth of drilling required to cover full depth of aquifer proposed to be tapped,probable yield and other information required including transportation of instrument and accesories to work site,engaging technical personal and labour required etc.,	Nos	3806.00	Rupees Three Thousand Eigh Hundred Six Only
2	600.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burden upto 20 M fixing of casing pipes, collars and cap with necessary cutting and threading including transportation of rig and supporting vehicals, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour .(excluding cost of casing pipes, collars, cap ect.) 0 to 50 m	Rmtr	350.00	Rupees Three Hundred Fifty Only
3	600.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burden upto 20 M fixing of casing pipes, collars and cap with necessary cutting and threading including transportation of rig and supporting vehicals, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour .(excluding cost of casing pipes, collars, cap ect.) 50 to 100 m	Rmtr	446.00	Rupees Four Hundred Forty Six Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

4	600.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burden upto 20 M fixing of casing pipes, collars and cap with necessary cutting and threading including transportation of rig and supporting vehicals, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour .(excluding cost of casing pipes, collars, cap ect.) 100 to 150 m	Rmtr	461.00	Rupees Four Hundred Sixty One Only
5	600.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burden upto 20 M fixing of casing pipes, collars and cap with necessary cutting and threading including transportation of rig and supporting vehicals, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour .(excluding cost of casing pipes, collars, cap ect.) 150 to 200 m	Rmtr	541.00	Rupees Five Hundred Forty One Only
6	600.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burden upto 20 M fixing of casing pipes, collars and cap with necessary cutting and threading including transportation of rig and supporting vehicals, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour .(excluding cost of casing pipes, collars, cap ect.) 200 to 250 m	Rmtr	640.00	Rupees Six Hundred Forty Only
7	600.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burden upto 20 M fixing of casing pipes, collars and cap with necessary cutting and threading including transportation of rig and supporting vehicals, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour .(excluding cost of casing pipes, collars, cap ect.) 250 to 300 m	Rmtr	707.00	Rupees Seven Hundred Seven Only
8	600.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burden upto 20 M fixing of casing pipes, collars and cap with necessary cutting and threading including transportation of rig and supporting vehicals, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour .(excluding cost of casing pipes, collars, cap ect.) 300 to 350 m	Rmtr	833.00	Rupees Eight Hundred Thirty Three Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

9	600.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burden upto 20 M fixing of casing pipes, collars and cap with necessary cutting and threading including transportation of rig and supporting vehicals, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour .(excluding cost of casing pipes, collars, cap ect.) 350 to 400 m	Rmtr	909.00	Rupees Nine Hundred Nine Only
10	240.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burden upto 20 M fixing of casing pipes, collars and cap with necessary cutting and threading including transportation of rig and supporting vehicals, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour .(excluding cost of casing pipes, collars, cap ect.) 400 to 420 m	Rmtr	1140.00	Rupees One Thousand One Hundred Forty Only
11	144.00	Providing and fixing 250mm dia PVC (casing pipe) As Per Direction of Engineer Incharge	Rmtr	2626.00	Rupees Two Thousand Six Hundred Twenty Six Only
12	600.00	Supply of ISI Mark 175mm nominal Bore, Plain end steel casing Pipe-grade of steel Fee 4100 of wakk thickness 504mm thick confirming to IS 4270:2001 and latest amendments, electric resistance welded steel electric or basic oxygen process in fandom length of 5 to 7mtr. Both ends threaded confirming to Is554/1985 one end fixed with socket confirming to IS 270:2001 and other end with screwed pipes. All pipes shall be reasonably free from defectes. The tubes shall be resonably straigth should be with ISI Marking Weighting 25.10 kg/mtr (Inclusive of all taxes and durties) Prices include Collar - medium duty. As Per Direction of Engineer Incharge	Rmtr	1338.00	Rupees One Thousand Three Hundred Thirty Eight Only
13	100.00	Providing 175mm Dia M.S. CollarAs Per Direction of Engineer Incharge	Nos	152.00	Rupees One Hundred Fifty Two Only
14	12.00	Providing 175mm dia Bore Cap CE (M) (As Per Direction of Engineer Incharge	Nos	101.00	Rupees One Hundred One Only
15	12.00	Atalanta suguna CRI KIRLOSKAR and other equipments pumps 10.00 HP/7.5 KV (20 stage) As Per Direction of Engineer Incharge	Nos	50455.00	Rupees Fifty Thousand Four Hundred Fifty Five Only
16	4440.00	Providing and fixing in trenches galvinised/mild steel tube 50mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for seperately) including cost of all materials, labour charges,HOM of equipment and testing complete as per specifications. Specification No. KBS 13.2.14/13.6 As Per Direction of Engineer Incharge	Rmtr	415.00	Rupees Four Hundred Fifteen Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

17	9000.00	Supplying and drawing 3 core flat PVC sheathed submersible pump cable maufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 to IS 8130-1984 and virgin grade PVC insulation and power coating extruded PVC sheathed suitable for working voltage upto 1100 volts with specified IS 694:1990 and confirming to the attwached GTP of group A 3CX4.0 sq.mm (As Per Direction of Engineer Incharge	Rmtr	128.00	Rupees One Hundred Twenty Eight Only
18	12.00	Providing and fixing in position 50mm Nominal bore non-return valve vertical type of approved make including cost of all materials,labour and HOM of equipment with all leads complete as per specificationsAs Per Direction of Engineer Incharge	Nos	1359.00	Rupees One Thousand Three Hundred Fifty Nine Only
19	12.00	Spplying and fixing 50mm GI Union.As Per Direction of Engineer Incharge	Nos	226.00	Rupees Two Hundred Twenty Six Only
20	12.00	Spplying and fixing 50mm GI Elbow.As Per Direction of Engineer Incharge	Nos	113.00	Rupees One Hundred Thirteen Only
21	12.00	Spplying and fixing 50mm GI Nipple.As Per Direction of Engineer Incharge	Nos	105.00	Rupees One Hundred Five Only
22	744.00	Spplying and fixing 50mm GI Hose colleresAs Per Direction of Engineer Incharge	Nos	104.00	Rupees One Hundred Four Only
23	12.00	Supplying and fixing 20" x 20" x 2.5" polished wood board made of not less than 15mm thick plank on both the sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., P.no.44 / I no. 6.6.6 As Per Direction of Engineer Incharge	Nos	305.00	Rupees Three Hundred Five Only
24	12.00	Supplying and fixing miniature circuit breakers on existing MCB distribution board using necessary fixing materials and 'C' type curve indicator ON/OFF energy cross-3 with short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.As Per Direction of Engineer Incharge	Nos	1955.00	Rupees One Thousand Nine Hundred Fifty Five Only
25	12.00	Supplying of TPST with rewirable porcelain channels in SM encloser made out of 14 SWG powder coated point of approved colour 32 amps (As Per Direction of Engineer Incharge	Nos	1818.00	Rupees One Thousand Eight Hundred Eighteen Only
26	12.00	Supplying and fixing LED type panel board indicating lamp with required colour suitable for 220 V AC 50 HZ 12/24 V DCAs Per Direction of Engineer Incharge	Nos	434.00	Rupees Four Hundred Thirty Four Only
27	12.00	Suppling fully automatic star delta starter unit push button type with suitable wires 2 conductors and adjustable thermal timer mounted on a common base plate held in steel enclosure for use on 400/440 volts phase and wired after fixing to the existing wooden board for motor. upto 12.5HPAs Per Direction of Engineer Incharge	Nos	6464.00	Rupees Six Thousand Four Hundred Sixty Four Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

28	12.00	Supplying and fixing single phase preventer using necessary wires over an existing panel board suitable for motar up to 20 HP capacities.As Per Direction of Engineer Incharge	Nos	752.00	Rupees Seven Hundred Fifty Two Only
29	240.00	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade multistrand copper conductor single core wire in open or concealed system of wiring as per IS 694:1990 & conforming to the attached GTP of group A. 4 sqmmAs Per Direction of Engineer Incharge	Mtrs	45.00	Rupees Forty Five Only
30	48.00	Supplying fixing and wiring heavy duty low voltage capacitors conforming to IS 2834 phase 400/440 volts grade, for power factor improvement of rotating machineryAs Per Direction of Engineer Incharge	Nos	404.00	Rupees Four Hundred Four Only
31	12.00	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C cotouts and other equipments on the meter board using 40mm dia 2.90 thick GI pipe 2.5 mtr long buried in a pit... The pit should be filled with equal proprotion of salt and charcoal 150mm alround the pipe to complete depth. The connection from the to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia As Per Direction of Engineer Incharge	Nos	3030.00	Rupees Three Thousand Thirty Only
32	96.00	Digging of trench of 0.36mtrs deepx0.5 mtrs wide refilling the trench to the required gorund level and consolidating etc., complete As Per Direction of Engineer Incharge	Mtrs	103.00	Rupees One Hundred Three Only
33	120.00	Supplying laying 1.1 KV class LT UG cable having aluminium conductor PVC insulated extruded inner shethed galvanised steel strip (excep 2cx 10 sqmm wire armoured) confirming to IS-3975:1990 (No. of strip indicated in GTP) and extruded PVC outer sheathed armoured cable with specified IS-1554,part-1:1988 and confirming to the attached GTP of group A 4 core 16 sq mm As Per Direction of Engineer Incharge	Mtrs	152.00	Rupees One Hundred Fifty Two Only
34	300.00	Labour charge for laying 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe/ on wall / on poles as required in existing trench/duct. 6 sq mm to 16 sq mmAs Per Direction of Engineer Incharge	Nos	12.00	Rupees Twelve Only
35	24.00	Supplying and fixing class-A(medium duty) GI pipe wall thickness not less then 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1KV class 40mmAs Per Direction of Engineer Incharge	Rmtr	338.00	Rupees Three Hundred Thirty Eight Only
36	12.00	Supplying and fixing LT cast iron pot heads suitable for 1.1KV class UG cable filled with necessary bitumen / insulating compound complete with terminals,clamps bolts and nuts and washer etc.,complete for 16 sq mm as per specificationsAs Per Direction of Engineer Incharge	Nos	273.00	Rupees Two Hundred Seven Three Only
37	36.00	Supplying and fixing porcelain fuse channel with cut out on the existing wooden block and wiring complete 63 ampsAs Per Direction of Engineer Incharge	Nos	229.00	Rupees Two Hundred Twenty Nine Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

38	401.27	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials upto a lead of 1000 meters, stacking serviceable and unserviceable materials seperately complete as per specifications. MORTH Specification No. 202As Per Direction of Engineer Incharge	Cum	962.00	Rupees Nine Hundred Sixty Two Only
39	601.91	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(b) / 2.3.5 As Per Direction of Engineer Incharge	Cum	481.00	Rupees Four Hundred Eighty One Only
40	2048.58	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (external work) - 50mm nominal OD pipes As Per Direction of Engineer Incharge	Mtrs	462.00	Rupees Four Hundred Sixty Two Only
41	241.00	Making connection of G.I.distribution branch with G.I.main of 25mm to 40mm. Nominal bore, including cutting and threading the pipes,providing and fixing Tee, nuts,labour for all item of works,testing and HOM of equipments complete as per specifications.As Per Direction of Engineer Incharge	Each	517.00	Rupees Five Hundred Seventeen Only
42	2651.00	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778 having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step solvent cement, trenching, refilling & testing of joints complete. (external work). - 20mm nominal OD pipesAs Per Direction of Engineer Incharge	Mtrs	168.00	Rupees One Hundred Sixty Eight Only
43	8000.00	Providing and fixing to wall, ceiling and floor Medium density polyethylene pipes 6.00 kgf/sq.cm working pressure 25mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.15.1 / 13.9As Per Direction of Engineer Incharge	Mtrs	138.00	Rupees One Hundred Thirty Eight Only
44	421.34	Refilling available around earth pipe lines,cables in layers mot exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. And lift upto 1.5m. Including cost of all labour complete as per specificationsAs Per Direction of Engineer Incharge	Cum	130.00	Rupees One Hundred Thirty Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

45	581.84	Loading and unloading of stone boulder/stone aggregates/sand/kanker/ moorum. KSRRB M100-1:Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1As Per Direction of Engineer Incharge	Cum	99.00	Rupees Ninety Nine Only
46	12.00	Providing and fixing in position brass gate valve with C.I.wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials,labour and HOM of equipments with all leads complete as per specifications. As Per Direction of Engineer Incharge	Each	1862.00	Rupees One Thousand Eigh Hundred Sixty Two Only
47	491.00	: Providing and fixing in position brass stop cock of approved quality 15mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.2 / 13.3As Per Direction of Engineer Incharge	Each	151.00	Rupees One Hundred Fifty One Only
48	300.95	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2.As Per Direction of Engineer Incharge	Cum	5462.00	Rupees Five Thousand Four Hundred Sixty Two Only
49	250000.00	Supplying water storage tanks made of virgin polymer (LLDPE) with two layers outer Black or Blue and inner White layer of approved quality and make, conforming to I.S.I./ISO/SSI specifications. As Per Direction of Engineer Incharge	Ltr	5.90	Rupees Five And Paise Ninety Only
50	250.00	Supplying, installation, testing and commissioning of solar hot water heater comprising of solar Flat Plate Collector (FPC) of size 2120x1040x100mm and stainless steel hot water storage tank with stainless steel heat exchanger absorber made of copper sheet and copper tube of following capacity aluminium box collector with appropriate capacity electrical back up arrangement excluding inlet and out let pipes.SS Model with 100mm thick of 48Kg/M3 density Rock wool insulation with 22SWG Aluminium cladding. 200 Liter capacity As Per Direction of Engineer Incharge	Nos	49086.00	Rupees Forty Nine Thousand Eighty Six Only
51	1376.79	Dismantling of cement concrete pavement by mechanical means using neumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperately complete as per specifcations. MORTH Specifcation No. 202 As Per Direction of Engineer Incharge	Cum	962.00	Rupees Nine Hundred Sixty Two Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

52	1388.97	Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3As Per Direction of Engineer Incharge	Cum	139.00	Rupees One Hundred Thirty Nine Only
53	679.32	Providing and fixing unplasticised PVC pipes with working pressure 10 kg/sq.cm with pipe fittings, clips, making good the floor, including cost of all materials, labour charges, HOM and testing complete as per specifications.-do- with 225mm outer dia KPWD S.R 2018-19 As Per Direction of Engineer Incharge	Mtrs	2044.00	Rupees Two Thousand Forty Four Only
54	66.44	Plain cement concrete M10 mix with crushed stone aggregate 40mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing including cost of materials, labour, HOM complete as per specifcations. MORTH Specifcation No. 408. As Per Direction of Engineer Incharge	Cum	4524.00	Rupees Four Thousand Five Hundred Twenty Four Only
55	125.60	Providing and laying reinforced cement concrete pipe NP2 for culverts including pointing ends, and fixing collars with cement mortar 1:2 including cost of materials, labour, HOM complete as per specifications, curing complete as per specifications. Specifications. As Per Direction of Engineer Incharge	Mtrs	1131.00	Rupees One Thousand One Hundred Thirty One Only
56	80.00	Constructing brick masonry circular type manhole 0.91 m internal dia at bottom, 1.67 m deep and 0.56m dia at top with table moulded non-modular bricks of 50 class designation 50 in cement mortar 1:4, inside cement plastered 12mm thick with cement mortar 1:3, finished with a floating coat of neat cement, foundation concrete M 10 using 40mm and downsize granite metal and making necessary channel in cement concrete M 50 with 20mm and downsize granite metal finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560mm internal diametre confirming IS :12592, total weight cover and frame to be not less than 182 kg, fixed in cement concrete 1:2:4, 20mm and downsize broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of mechineries complete as per specifications. (Excavation, footrests and 12mm thick cement plaster on the external surface shall be paid seperately) Specification No. KBS 12.4KPWD As Per Direction of Engineer Incharge	Nos	25998.00	Rupees Twenty Five Thousand Nine Hundred Ninety Eight Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

57	180.00	Constructing brick masonry inspection chamber for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete M 15 with 20mm and downsize granite metal, foundation concrete M 5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS. – do – 450x450mm and 450mm depth (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 450x450mAs Per Direction of Engineer Incharge	Nos	5674.00	Rupees Five Thousand Six Hundred Seventy Four Only
58	120.00	Making connection of drain or sewer line of size 230 to 300 mm external dia with existing manhole including breaking into and making good the walls, floors with cement concrete M 15 with 20mm and downsize granite metal, cement plastered on both sides of mix 1:3, finished with a floating coat of neat cement, and making necessary channels for the drain, including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS As Per Direction of Engineer Incharge	Nos	3734.00	Rupees Three Thousand Seven Hundred Thirty Four Only
59	80.00	Providing 20mm square M.S footrest and fixing in manhole with M 10 cement concrete block of 20x20x10cms, using 20mm and down size metal of size including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS 12.4.6 P.No73I.NO.11.44	Nos	295.00	Rupees Two Hundred Ninety Five Only
60	750.00	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials, labour charges, HOM of acquirements and testing complete as per specifications. - 110mm dia	Mtrs	465.00	Rupees Four Hundred Sixty Five Only
61	833.38	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifcations.As Per Direction of Engineer Incharge	Cum	130.00	Rupees One Hundred Thirty Only
62	1932.38	Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifcations. MORTH -100/ Chapter 1 As Per Direction of Engineer Incharge	Cum	99.00	Rupees Ninety Nine Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

63	697.85	Providing, laying, spreading and compacting specified graded sand, gravel or any other course material 60% and crushed stone aggregates of granite / trap / basalt 40% in sub-base course including premixing the material at OMC in mechanical mixer (Pug mill), carriage of mixed material up to 1km, spreading in uniform layers with motor grader on a prepared base and compacting with power roller to achieve the desired density including all materials, labour, HOM of machinery, lighting, guarding, barricading and maintenance of diversion complete as per specifications. MORTH Chapter 4As Per Direction of Engineer Incharge	Cum	1336.00	Rupees One Thousand Three Hundred Thirty Six Only
64	10472.17	Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3As Per Direction of Engineer Incharge	Cum	139.00	Rupees One Hundred Thirty Nine Only
65	6433.94	Compaction KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. MORTH / Chapter 3 As Per Direction of Engineer Incharge	Sqm	6.00	Rupees Six Only
66	965.09	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications. Clause 401 of MORTH V Revision.As Per Direction of Engineer Incharge	Cum	2015.00	Rupees Two Thousand Fifteen Only
67	965.09	Construction of dry lean cement concrete mix CC1:5:10 with OPC cement @160Kgs, with 25mm and down size graded granite metal coarse aggregate at 0.86cum and fine aggregates @ 0.58cum Sub- base over a prepared sub-grade with (coarse and fine aggregate conforming to IS: 383) aggregate cement ratio not to exceed 15:1. Aggregate gradation after blending to be as per Table 600-1, cement content not to be less than 160 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonnes vibratory roller, finishing and curing complete as per specifications. . MORTH Specification No. 601As Per Direction of Engineer Incharge	Cum	3924.00	Rupees Three Thousand Nine Hundred Twenty Four Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

68	965.09	Constructing un-reinforced, plain cement concrete for pavements using Grade concrete M30 over a prepared base with OPC coarse aggregate at 0.69 cum, fne aggregates at 0.46 cum,Coarse and fne aggregate conforming to IS:383-2016, with Superplastizer at 3 lts conforming to IS 9103-2008. mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fxed side form work (steel channel, laying and fxing of 125 micron thick polythene flm, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and fnished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints,including groove cutting charges, joint fller, separation membrane of impermiable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, fnishing to lines and grades, textured with texturing machine, and curing including cost of all materials, labour,hire charges of machineries,all lead & lift charges etc., complete as per	Cum	5263.00	Rupees Five Thousand Two Hundred Sixty Three Only
69	6433.94	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift.. KPWD S.R 2018-19 As Per Direction of Engineer Incharge	Sqm	73.00	Rupees Seventy Three Only
70	572.63	Plain cement concrete M10 mix with crushed stone aggregate 40mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing including cost of materials, labour, HOM complete as per specifcations. MORTH Specifcation No. 408. As Per Direction of Engineer Incharge	Cum	4527.00	Rupees Four Thousand Five Hundred Twenty Seven Only
71	1355.39	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fne aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specifcation No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specifcations. -do- Wall & bottom thickness 15cmAs Per Direction of Engineer Incharge	Cum	7151.00	Rupees Seven Thousand One Hundred Fifty One Only
72	88.56	TMT/MS Bar Reinforcement KSRRB M2200-6. Supplying, fitting and placing TMT bar reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specificationsMORTH SpecificationAs Per Direction of Engineer Incharge	Tonne	73050.00	Rupees Seventy Three Thousand Fifty Only
73	2507.38	Providing & laying precast drain cover slab of 100 mm thickness in CM 1:2 including cost of all materials, labour, curing, transportation, loading, unloading etc, complete as per the Directions of the Engineer In Charge.(0.90 x 0.60 x 0.10) (Approved Data rate)	Sqm	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only

Executive Engineer
RRNagara Division
BBMP

Signature of the contractor

74	702.00	Providing & laying precast drain cover slab of 250 mm thickness in CM 1:3 including cost of all materials, labour, curing, transportation, loading, unloading etc, complete as per the directions of the Engineer In Charge.(1.2 x 0.60 x 0.10) Approved Data rate(18-11-2016)	Sqm	5418.00	Rupees Five Thousand Four Hundred Eighteen Only
75	2.00	SUPPLYING AND FIXING OF LEG PRESS DOUBLE OF SAFE AREA : 2.8MTR X 1.5MTR, CENTER PIPE : 100 NB GI B-CLASS PIPE, SEAT FRAME : 32 NB GI B-CLASS Pipe, BLOCK REST : LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN: Seamless Pipe & Round Bar, BEARINGS : PREMENENT SEALED OF REPUTED MAKE (FAG/SKF), STOPER : PU ROD, NUT BLOTS CAP: Nylon 66 injection moulded, NUT BOLTS : HIGH TENSILE STELL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70-80 MICRON THICKNESS AS PER ENGINEER IN CHARGE OF THE WORK.	Nos	90900.00	Rupees Ninety Thousand Nine Hundred Only
76	3.00	SUPPLYING AND FIXING OF FUN WALKER DOUBLE OF SAFE AEA : 3MTR X 2MTR, MAIN FRAME : 100 NB GI B-Class Pipe, LEG FRAME:32 NB GI B-CLASS Pipe, HANDLE FRAME :25 NB GI B-CLASS Pipe, FOOT REST: LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : SEAMELESS Pipe & Round Bar, NUT BOLT CAP : Nylon 66 injection moulded, BEARING: PERMANANT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70-80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK	Nos	151500.00	Rupees One Lakh(s) Fifty One Thousand Five Hundred Only
77	2.00	SUPPLYING AND FIXING OF PENDULUM DOUBLE OF SAFE AEA : 2.5MTR X 1MTR, MAIN FRAME : 100 NB GI B-Class Pipe, LEG FRAME:40 NB GI B-CLASS Pipe, HANDLE FRAME :25 NB GI B- CLASS Pipe, SEAT: LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : SEAMELESS Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARING: PERMANANT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70-80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK	Nos	90900.00	Rupees Ninety Thousand Nine Hundred Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

78	2.00	SUPPLYING AND FIXING OF SHOULDER PRESS DOUBLE OF SAFE AEA : 4MTR X 2.5MTR OF CENTRE PIPE: 100 NB GI B-Class Pipe, SEAT FRAME : 32 NB GI B-Class Pipe, HANDLE FRAME:32 NB & 15 NB GI B-CLASS Pipe, Handle Cover : TPEE injection moulded, SEAT REST: LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : SEAMELESS Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARING: PERMANANT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, NUT BOLT CAP : Nylon 66 injection moulded, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70-80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK	Nos	181800.00	Rupees One Lakh(s) Eighty One Thousand Eight Hundred Only
79	2.00	SUPPLYING AND FIXING OF CYCLE TWO WAY OF SAFE AEA : 2.5MTR X 1MTR, MAIN FRAME : 100 NB GI B-Class Pipe, ARM FRAME:40 NB GI B-CLASS Pipe, HANDLE FRAME :20 NB GI B- CLASS Pipe, SEAT: LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : SEAMELESS Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARING: PERMANANT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70-80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK	Nos	106050.00	Rupees One Lakh(s) Six Thousand Fifty Only
80	3.00	SUPPLYING AND FIXING OF TAI CHI SPINNER DOUBLE OF SAFE AEA : 2MTR DIA, MAIN FRAME : 100 NB GI B-Class Pipe, HANDLE FRAME:32 NB GI B-CLASS Pipe, SPINNING RING: LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : SEAMELESS Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARING: PERMANANT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70-80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK	Nos	90900.00	Rupees Ninety Thousand Nine Hundred Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

81	2.00	SUPPLYING AND FIXING OF TWISTER THREE WAY OF SAFE AEA : 2.5 MTR DIA, MAIN FRAME : 100 NB GI B-Class Pipe, ARM FRAME:32 NB GI B- CLASS Pipe, HANDLE FRAME:20 NB GI B-CLASS Pipe, TWISTER DISC: LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : SEAMELESS Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARING: PERMANANT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70-80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK	Nos	90900.00	Rupees Ninety Thousand Nine Hundred Only
82	1.00	SUPPLYING AND FIXING OF CHEST PRESS DOUBLE OF SAFE AEA : 4MTR X 2.5MTR OF CENTRE PIPE: 100 NB GI B-Class Pipe, SEAT FRAME : 32 NB GI B-Class Pipe, HANDLE FRAME:32 NB & 15 NB GI B-CLASS Pipe, Handle Cover : TPEE injection moulded, SEAT REST: LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : SEAMELESS Pipe & Round Bar, BEARING: PERMANANT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS CAP : Nylon 66 injection moulded, NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70-80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK	Nos	181800.00	Rupees One Lakh(s) Eighty One Thousand Eight Hundred Only
83	3.00	SUPPLYING AND FIXING OF FUN ROVER OF SAFE AEA : 2.5MTR X 1.5MTR, MAIN FRAME : 80 NB GI B-Class Pipe, SEAT FRAME:80 NB GI B-CLASS Pipe, HANDLE FRAME: 32NB GI B- CLASS PIPE, SEAT: LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : SEAMELESS Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARING: PERMANANT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70-80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK	Nos	62620.00	Rupees Sixty Two Thousand Six Hundred Twenty Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

84	1.00	SUPPLYING AND FIXING OF FUN RIDER OF SAFE AEA : 2.5MTR X 1.5MTR, MAIN FRAME : 80 NB GI B-Class Pipe, SEAT FRAME:80 NB GI B-CLASS Pipe, HANDLE FRAME: 32NB GI B- CLASS PIPE, SEAT: LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : SEAMELESS Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARING: PERMANANT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70-80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK	Nos	151500.00	Rupees One Lakh(s) Fifty One Thousand Five Hundred Only
85	2.00	SUPPLYING AND FIXING OF STEP TRAINER OF SAFE AEA : 3MTR X 1.5MTR, MAIN FRAME : 100 NB GI B-Class Pipe, BOTTOM FRAME:40 NB GI B-CLASS Pipe, HANDLE FRAME: 32NB &15 NB GI B- CLASS PIPE, Handle cover: TPEE injection moulded, FOOTREST: LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : SEAMELESS Pipe & Round Bar, NUT BOLTS CAP : Nylon 66 injection moulded, BEARINGS: PERMANANT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70-80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK	Nos	183315.00	Rupees One Lakh(s) Eighty Three Thousand Three Hundred Fifteen Only
86	2.00	SUPPLYING AND FIXING OF ROLLING BARREL DOUBLE OF SAFE AEA : 2.8MTR X 1.5MTR OF CENTRE PIPE: 100 NB GI B-Class Pipe, SEAT FRAME : 32 NB GI B-Class Pipe, BACK REST: LLDP Plastic, SEAT REST: LLDP Plastic, FOOT REST: LLDP Plastic, PIPE CAP : Nylon 66 injection moulded, BEARING CAP : Nylon 66 injection moulded, BEARING HOUSING AND PIN : SEAMELESS Pipe & Round Bar, BEARING: PERMANANT SEALED OF REPUTED MAKE (FAG/SKF), NUT BOLTS CAP : Nylon 66 injection moulded, NUT BOLTS : HIGH TENSILE STEEL, GALVANISED NUT BOLTS, POWDER COAT : DONE BY PURE POLYURETANE POWDER WITH 70-80 MICRON THICKNESS AS PER ENGINEER INCHARGE OF THE WORK	Nos	145440.00	Rupees One Lakh(s) Forty Five Thousand Four Hundred Forty Only
87	557.66	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification	Sqm	1303.00	Rupees One Thousand Three Hundred Three Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

88	29.40	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications(Page - 25/ Item no.5.6)	Cum	4920.00	Rupees Four Thousand Nine Hundred Twenty Only
89	19.51	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications. (Page - 13/ Item no.4.6)	Cum	5870.00	Rupees Five Thousand Eight Hundred Seventy Only
90	857.74	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification	Sqm	1263.00	Rupees One Thousand Two Hundred Sixty Three Only
91	130.00	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete	Nos	354.00	Rupees Three Hundred Fifty Four Only
92	115.50	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineerin - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete)(Page - 266/ Item no.37.2)	Mtrs	920.00	Rupees Nine Hundred Twenty Only
93	210.00	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint.(Page - 266/ Item no.37.4)	Mtrs	437.00	Rupees Four Hundred Thirty Seven Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

94	196.00	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint.(Page - 266/ Item no.37.3)	Sqm	765.00	Rupees Seven Hundred Sixty Five Only
95	18.57	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeeding 50 m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and nealty dressed as per specifications	Cum	171.00	Rupees One Hundred Seventy One Only
96	73.30	KSRB -2-2.1 : Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. after breaking of clods complete as per specifications.	Cum	326.00	Rupees Three Hundred Twenty Six Only
97	9.20	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 5.75 cum machine mixed, concrete laid in layers not exceeding 15 cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specification.	Cum	5565.00	Rupees Five Thousand Five Hundred Sixty Five Only
98	13.28	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @320kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459cum, with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walla (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, structs, buttresses, string or lacing courses, parpets, coping, bed blocks, anchor, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing complete as per specification. Specification No. KBS 4.1, 4.6 (P.No. 13/4.11)	Cum	6594.00	Rupees Six Thousand Five Hundred Ninety Four Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

99	40.30	Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides & soffits of beams, beam hauncing cantilever girders, bressumers & lintels & not exceeding 1.0 in depth including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2	Sqm	319.00	Rupees Three Hundred Nineteen Only
100	72.00	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.3	Sqm	480.00	Rupees Four Hundred Eighty Only
101	3.10	Providing and laying in position reinforced cement cocnrete of design mix M20 with OPC cement @ 27.20 Kgs with 12mm & down sizes graded grantie metal coarse aggregated @ 0.5865 cum & fine aggregates, @ 0.391 Cum with super super plastisiser @ 0.225 Ltrs maichine mixed well compacted plain chajja 8.50 Cms avg thickness, up to ground floor level including removing centering, shuttering, strutting, propping etc., and removal of form work for cost of all materials, laobur HOM of machinary, curing complete as per specification.Ground floor	Sqm	480.00	Rupees Four Hundred Eighty Only
102	6.20	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels of all shapes & sizes, at all elevations & heights.	Sqm	352.00	Rupees Three Hundred Fifty Two Only
103	1.56	Providing TMT Steel reinforcement for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. FOR TMT Bars Fe- 500 Ground Floor	Tonne	77410.00	Rupees Seventy Seven Thousand Four Hundred Ten Only
104	29.30	Providing & Constructing Granite/ trap/basalt size stone Masonary in basement with Cement morter 1:8 edges of stone chistle dressed in courses not less than 15 cms high, bond stones at two mtr apart in each course including cost of all materials, labour, curing complete as per specifications	Cum	5981.00	Rupees Five Thousand Nine Hundred Eighty One Only
105	29.40	Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. In depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5m. Inluding cost of all labour complete as per speicifications.No.KBS 2.9	Cum	219.00	Rupees Two Hundred Nineteen Only
106	113.50	Providing and constructing Pre cast solid blocks with Compressive strength not less than 35 kg/ sqm with cement morter 1:4 masonary (quion, Jamb, closer block) with solid concrete blockx of size 40 x 15 x 20 cms confirming to IS 2185/1965 in super structures including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	1008.00	Rupees One Thousand Eight Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

107	55.02	Providing & constructing non load bearing walls cemect concrete solid blocks with compressive strength not less than 35 kg/sqm with cement morter 1:4 (jamb, closer blocks) with blocks of size 40X10X20. (LXBXH) confirming to I.S. : 2185/1965 in super structure including cost of materials, labour charges, scaffolding, curing complete as per specification.	Sqm	885.00	Rupees Eight Hundred Eighty Five Only
108	149.30	Providing 18mm thick cement plaster in single coat with cement mortor 1:3 to Brick masonary including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	301.00	Rupees Three Hundred One Only
109	169.30	Providing 18mm thick cement plaster in single coat with cement mortor 1:4, to brick masonry including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(internal)	Sqm	285.00	Rupees Two Hundred Eighty Five Only
110	56.00	Providing 12mm thick cement plaster in single coat with cement mortor 1:3, to ceiling including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. GG	Sqm	256.00	Rupees Two Hundred Fifty Six Only
111	69.12	Providing INTEGRAL CRYSTALINE Waterproofing treatment to the sunken portion of toilets. Using Crystalline Slurry of approved make @ 1.40 kg per SQM in two coats (0.7 Kg per coat) confirming to ASTM S 1202 & DINV 18998 standards.	Sqm	469.00	Rupees Four Hundred Sixty Nine Only
112	25.83	Providing and fixing of factorymade 30 mm P.V.C door frame of size 50x47 mm with a wall thickness of 5 mm made out of extrued 5 mm rigid PVC foamsheet metered cut at cornwers & jointed 2 nos 150 mm long brackets of 15 x 15 mm MS Square tube, the entire door frame to be reinforced with 19 x 19 m square tube of 19 gauge. the door frame to be fixed to the wall using MS screws of 65 /80 mm size complete as per manufacturers specification& directions of Engineer in charge.	Sqm	510.00	Rupees Five Hundred Ten Only
113	23.90	Providing & fixing 30mm thick factory made rigid foam Panelled Door Shutters made from M.S. tube of 19 gauge thickness, size 19 x 19mm for styles and 15 x 15mm for top and bottom rails, covered with heat moulded PVC channel of 5mm thick sheet & 30 x 50mm wide to form styles & 5mm thick & 75mm wide PVC Sheets for top rail, lock rail & bottom rail on either side & 5mm thick 20mm wide PVC sheet as gap insert for top rail & bottom rail, Panelling of 5mm thick PVC sheet fitted in the M.S. Frame, Sealed to the styles & rails with 5 x 30mm PVC sheet beading on either side & joined together with solvent cement adhesive etc., Complete as per manufacturers specification & direction of Engineer-in-charge fixed to frames with 3 nos of 75 mm Aluminium hinges. GG	Sqm	3029.00	Rupees Three Thousand Twenty Nine Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

114	5.10	Providing and fixing in position in cement concrete 1:3:6 steel glazed windows and ventilators side hung/top hung fully openable as per approved drawings using Z angles of 25x33x3mm, weighing 1.419 kg/m both for outer and inner frames and central mullion section of size 25x46x3mm weighing 2.28 Kg/m duly providing T section 19x19x3mm weighing 0.839 kg/m for glazing of windows not more than 34 cms. c to c including providing and fixing 4mm. thick reeded glass with teakwood beading of required size, all steel sections should confirm to I.S. 7452 : 1990, 4nos, of holdfasts of approved size, section should be cut to length welded and electrically grinded subdividing frames of unit shall be tenonned and revetted into the frames electrically. All the steel surface shall be throughly cleaned free of rust and painted with one coat of anti-corosive paint and finishing with two coats of ready mix paint of approved colour and make including cost of materials, fixtures, labour, and HOM of machinery complete as per specifications.	Sqm	4252.00	Rupees Four Thousand Two Hundred Fifty Two Only
115	5.40	Providing and fixing in position black cuddapah slab / Shahabad Slab/Thandur blue slab 4 cms thick for roofing laid to line and level over wooden rafters or RCC battens pointing exposed joints with cement mortar 1:4 including cost of materials, labour, curing complete as per specifications.	Sqm	694.00	Rupees Six Hundred Ninety Four Only
116	57.00	Providing ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick cement mortor 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. size 30x30cms	Sqm	1320.00	Rupees One Thousand Three Hundred Twenty Only
117	85.70	Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications.	Sqm	1391.00	Rupees One Thousand Three Hundred Ninety One Only
118	84.00	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications.	Sqm	120.00	Rupees One Hundred Twenty Only
119	56.00	Providing and applying two coats with oil bound washable distemper of approved brand and shade on Ceiling surface including priming coat with distemper primer after throughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications.	Sqm	129.00	Rupees One Hundred Twenty Nine Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

120	149.30	Water proof cement paint KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint with primer of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.	Sqm	111.00	Rupees One Hundred Eleven Only
121	8.00	Providing and fixing white vitreous china clay, water closet Indian type (Squatting pan) of size 580mm with footrests, 100mm S or P trap, (approved make) cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	Each	1452.00	Rupees One Thousand Four Hundred Fifty Two Only
122	3.00	Providing and fixing white vitreous china clay, flat back, lipped front urinal basin of 430x260x350mm with 5 litres PVC automatic flushing cistern, C.I / M.S brackets, standard flush pipe and C.P. brass spreaders with brass unions and G.I. clamps complete painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11	Each	3351.00	Rupees Three Thousand Three Hundred Fifty One Only
123	18.00	Providing & fixing CI Nahani trap of approved make confirming to ISI specification and construction of cistren in M 15 as per directions	Each	273.00	Rupees Two Hundred Seventy Three Only
124	20.00	Providing and fixing in position CP bib cock of approved quality 20 mm nominal bore including cost of all materials, labour and HOM of equipments with alll leads complete as per specifications.	Each	189.00	Rupees One Hundred Eighty Nine Only
125	4.00	Providing and fixing white vitreous china clay, flat back wash basin size 550x400mm with a single 15mm C.P brass pillar tap with C.I / M.S brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11	Nos	3295.00	Rupees Three Thousand Two Hundred Ninety Five Only
126	20.00	Providing and fixing to wall, ceiling and floor , Medium density polyethylene pipes 6.00 kgf /sqcm working pressure	Mtrs	356.00	Rupees Three Hundred Fifty Six Only
127	35.00	Providing and fixing to wall, ceiling and floor , Medium density polyethylene pipes 6.00 kgf /sqcm working pressure	Mtrs	415.00	Rupees Four Hundred Fifteen Only
128	45.00	KSRB 13-9 : Providing and fixing to wall, ceiling and floor , Medium density polyethylene pipes 6.00 kgf /sqcm working pressure	Mtrs	491.00	Rupees Four Hundred Ninety One Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

129	45.00	Providing and fixing to wall, ceiling and floor chlorinated poly vinyl chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all cpvc plain and brasss threaded fittings including fixing thepipes with the clamp at 1.00mtr spacing . This includes joining of pipes fittings with one set of cpvc solvent cement and testing of joints complete (Internal works) (Concealed work including cutting chases and good the walls etc.)A)15mm dia pipe nominal OD pipes	Mtrs	225.00	Rupees Two Hundred Twenty Five Only
130	35.00	Providing and fixing to wall, ceiling and floor chlorinated poly vinyl chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all cpvc plain and brasss threaded fittings including fixing thepipes with the clamp at 1.00mtr spacing . This includes joining of pipes fittings with one set of cpvc solvent cement and testing of joints complete (Internal works) (Concealed work including cutting chases and good the walls etc.) B)20 mm dia pipe nominal OD pipes	Mtrs	256.00	Rupees Two Hundred Fifty Six Only
131	15.00	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) NB including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification no: KBS 13.2.6/ a) of 20mm dia	Nos	367.00	Rupees Three Hundred Sixty Seven Only
132	15.00	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) NB including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification no: KBS 13.2.6/ b) of 25mm dia	Each	490.00	Rupees Four Hundred Ninety Only
133	2000.00	Polyethylene water storage tank of specified capacity and make	Nos	5.00	Rupees Five Only
134	25.00	Providing and fixing to wall, ceiling and floor chlorinated poly vinyl chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all cpvc plain and brasss threaded fittings including fixing thepipes with the clamp at . This includes joining of pipes fittings with one set of cpvc solvent cement and testing of joints complete (External works) 20 mm dia pipe nominal OD pipes	Mtrs	159.00	Rupees One Hundred Fifty Nine Only
135	35.00	Providing and fixing to wall, ceiling and floor chlorinated poly vinyl chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all cpvc plain and brasss threaded fittings including fixing thepipes with the clamp at . This includes joining of pipes fittings with one set of cpvc solvent cement and testing of joints complete (External works) 25 mm dia pipe nominal OD pipes	Mtrs	195.00	Rupees One Hundred Ninety Five Only
136	15.00	Providing and fixing to wall, ceiling and floor , high density polyethylene pipes 6.00 kgf /sqcm working pressure 110 mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor in b) 110 mm dia	Mtrs	256.00	Rupees Two Hundred Fifty Six Only

Executive Engineer
RRNagara Division
BBMP

Signature of the contractor

	4.00	Providing stone ware gully trap of approved quality and fixing in C C 1:2:4 and plastering with C M 1:3 where ever necessary (Rate including cost of all materials, fixtures and lead). Size: 15 cm x 10 cm	Each	207.00	Rupees Two Hundred Seven Only
138	8.00	Constructing brick masonry inspection chamber 450x450mm, and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover with frame (light duty) 455x450 mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete M15 with 20mm and downsize granite metal, foundation concrete M5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications.	Nos	9261.00	Rupees Nine Thousand Two Hundred Sixty One Only
139	2.00	Supplying, installation, testing and commissioning of solar hot water heater comprising of solar Flat Plate Collector (FPC) of size 2120x1040x100mm and stainless steel hot water storage tank with stainless steel heat exchanger absorber made of copper sheet and copper tube of following capacity aluminium box collector with appropriate capacity electrical back up arrangement excluding inlet and out let pipes.SS Model with 100mm thick of 48Kg/M3 density Rock wool insulation with 22SWG Aluminium cladding. 200 Liter capacity I.No 8.3.3 300 Liter capacity P.No 51 & 52	Each	60593.00	Rupees Sixty Thousand Five Hundred Ninety Three Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP